



Procurement Services
Lucas Administrative Center, 617
1 Nunn Drive
Highland Heights, KY 41099
859.572.6605
FAX 859.572.6995

ADDENDUM NO: 2

IFB/RFP No: NKU-51-19 and NKU-52-19

Commodity: Nunn Hall and FA Passenger Elevator Mods

Date: 8/14/2019

Due Date: 8/27/2019 @ 2PM

BIDDER/RESPONDER SHALL CONFORM TO THE FOLLOWING CHANGES AS SAME SHALL BECOME BINDING UPON THE CONTRACT TO BE ISSUED IN RESPONSE TO THIS INVITATION FOR BID.

We have changed the bid date to 8/27/2019 @ 2 PM ET.

The following items apply to both projects.

1. Refer to Section 142200, 2.04 Operation:

Add the following:

M. New-Pushbutton Crossover Network: Provide an interim crossover network to interface new and old group supervisory systems for purposes of cross cancellation of registered car and hall calls until modernization of individual group is complete. System shall immediately assign hall calls to both existing and modernized elevators and cancel call from both systems when either system cancels the call. Cross cancellation systems which assign calls to existing and modernized cars sequentially are not acceptable.

2. Refer to Section 142200: 2.01.A Supervisory Control and 2.04.A:

Delete the word "duplex" from each section.

3. Can NKU provide a summary of further detail on the cab interior such as what type of finish they are on the cab walls, the type of reveals and what type of ceiling NKU is looking for? Or would NKU be able to provide a cab allowance to include in the modernization bid?

The following supplements/modifies information contained in Section 2.09 Car Enclosure:

Ceiling: Stainless steel drop ceiling with 6 led lights.

Stainless steel doors and control panels

Walls: Plastic laminate full height panels on the 3 interior walls with stainless steel vertical reveals. Plastic laminate to be selected by NKU from full line offerings Wilsonart, Formica or equal. Grade 2 specialty

Toe Kick: Stainless steel

Handrails: Flat stainless steel

Floors – Luxury Vinyl Tile (LVT). To be selected by NKU full line offerings, Commercial Grade 0.125" thickness.

4. Is the intent of the specification to provide one full height lockable barricade that fits inside the elevator doors at one color of NKU's choosing for each project?

Provide an 8' high, lockable barricade for each project. Color to be selected by NKU Planning, Design and Construction.

END OF ADDENDUM