



Procurement Services  
Lucas Administrative Center, 617  
1 Nunn Drive  
Highland Heights, KY 41099  
859.572.6605  
FAX 859.572.6995

**ADDENDUM NO: 1**

**IFB/RFP No:** NKU-70-18

**Commodity:** SU 104 A/V

**Date:** 6/4/2018

**Due Date:** 6/11/2018

***BIDDER/RESPONDER SHALL CONFORM TO THE FOLLOWING CHANGES AS SAME SHALL BECOME BINDING UPON THE CONTRACT TO BE ISSUED IN RESPONSE TO THIS INVITATION FOR BID.***

**Please see the attached sign-in sheet from the pre-bid meeting**

**Please see the attached answers to questions from CMTA**

**Ryan Straus**  
Bid Specialist  
Procurement Services  
Northern Kentucky University  
617 Lucas Administrative Center  
Highland Heights, KY 41099  
O: (859) 572-6605  
F: (859) 572-6995

**THE END**

NKU-70-18

Student Union AV - GOVERNANCE ROOM

Pre-Bid Meeting Sign-In Sheet

5/30/2018 @ 10:00 am

PLEASE PRINT INFORMATION LEGIBLY. THANK YOU.

NAME	COMPANY	PHONE NUMBER	E-MAIL
1 Trish Bradley	Creative Image Tech	502-797-0107	tbradley@cit.ie
2 Gary Fliedner	Creative Image Tech	502-487-8039	gfliedner@cit.ie
3 Lisa Ratliff	AVT Systems	859-339-2689	lisa.ratliff@avsystems.com
4 Michael Cunningham	SoundCom Systems	513-313-4807	mcunningham@soundcom.net
5 Justin Wogren	Radiant	937-604-5166	<del>justin</del> justin.wogren@radianttech.net
6 Bill Tocci	RAD/AVT	800-348-4008	Bill.Tocci@RAD/AVTTECH.NET
7 Brian Meyer	AVI Systems	513.578.6500	brian.meyer@avisystems.com
8			
9			
10			

## NKU Governance Room AV Refresh – Addendum #1

6/4/18

### Provide the following Unit Prices with bid:

1. Projector as specified
  2. Projection Screens
  3. Transmitter - decora style for wall plates
  4. 1 Year of additional warranty
  5. Fiber tie lines each
  6. Cobra net card/connection at West-07 wall plate
  7. X panel license
  8. 10.1" Touch panel
- 
1. Drawings :
    - **The rack elevations labeled as “EXISTING RACKS” are intended to be for reference. The rack elevations labeled as “NEW RACKS” are intended to represent what the final product of the racks will be. Bidders shall use the flow diagram and the rack elevations to understand what equipment is new and what is existing to remain understanding that some of the gear in the racks is used for other spaces in the building.**
  2. Plates:
    - **New custom plate types shall be aluminum with etched labels that will be reviewed and approved during submittal phase of the project.**
    - **Provide strain relief at North-01 and West-07 wall plate.**
  3. Connector types:
    - **Neutrik connectors are preferred by the University, refer to the wall plate details for connector requirements.**
  4. Box dimensions:
    - **All box and custom wall plate dimensions and screw hole locations shall be field verified prior to ordering to ensure compatibility.**
  5. Lectern:

- a. Existing lectern shall be reworked and reused. A new pass through 2RU panel is required to allow for the connection of the new snake to the lectern then on to patch cables to pass through the lectern cubby.**
6. The new network switch for the control network shall be Contractor-Provided per NKU specs. Cisco model WS-C3560CX-12PC-S shall be provided. Provisioning shall be in accordance with NKU IT requirements.
7. All drywall work necessary for the projection screens will be by NKU. AV contractor to coordinate with NKU.
8. Existing wall plate EAST-05 is existing to remain. This plate shall be integrated into the new DSP to maintain existing functionality.